

Socket Combination PCM53-ISO

Socket combination with insulation monitor for operating Dynawatt generators and underfloor generators up to 9 kVA.

// Operating hours meter
// Insulation monitor
// IP44

Socket combination in plastic housing with insulation monitor and operating hours counter for operating underfloor generators from 9 kVA with 2 Schuko outlets and IP44.

Technical Information

Number of Outputs, CEE 16 A	0*
Number of Outputs, CEE 32 A	0*
Number of Outputs, Cable Gland	2*
Number of Outputs, Schuko	2*
Connection Type, Input	Cable Gland
Hour Meter	Yes
Insulation Monitor	Yes
Number of Circuit Breakers C16A-4P	0
Number of Circuit Breakers C32A-4P	0
Number of Circuit breakers B16A-2P	2
Number of Relays	1
Number of inputs	1
Dimensions (L x W x H)	305 x 260 x 130 mm
Weight	5 kg

*In the chosen option