

Socket Combination PCM69-ISO-16/32A

Socket combination with insulation monitor for operating underfloor generators from 9 kVA.

// Operating hours meter
// Insulation monitor
// IP44

Socket combination in plastic housing with insulation monitor and operating hours counter for operating underfloor generators from 9 kVA with 3 Schuko outlets and one CEE 16 A and one CEE 32 A outlet each and IP44.

LEAB by Micropower Group

Technical Information

Number of Outputs, CEE 16 A	1*
Number of Outputs, CEE 32 A	1*
Number of Outputs, Cable Gland	0*
Number of Outputs, Schuko	3*
Connection Type, Input	Cable Gland
Hour Meter	Yes
Insulation Monitor	Yes
Number of Circuit Breakers C16A-4P	1
Number of Circuit Breakers C32A-4P	1
Number of Circuit breakers B16A-2P	3
Number of Relays	1
Number of inputs	1
Dimensions (L x W x H)	520 x 225 x 230 mm
Weight	6.98 kg

*In the chosen option